BRUHAT BANGALORE MAHANAGARA PALIKE, YALAHANKA ZONE

Executive Engineer,Byatarayanapura Division, B.B.M.P., Bangalore - 92

Tender Notification No. **Sl. No.:** 65.

BBMP/EE/Btp/Ten/02/2012-13, dt: 15-05-12

DRAFT SCHEDULE-B

Name of Work :- Estimate for the work of Construction of RCC drain at Ayappa swamy Temple in Ward No. 7.Kodigehalli Sub Division Est.Cost Rs: 750000.00 Job Code No: 007-12-000050

Sl. No	Approved Quantity as per Estimate	Discriptions of Items	Unit	Sanctioned Rates as per Estimate	Rates Quoted	
				Rs.	Figures	In Words
1	81.00	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3. (P.No.149, I.No.19.1 of PW,P&IWTD S.R 2011-12)	Cum	62.86		
2	234.00	Earth work excavation for foundation of buildings, culverts, water supply, sanitary lines and slectrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m. In depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking specification. (P-5,I-2.4 PWD SR 2011-12)	Cum	217.08		
3	17.55	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15cms. thick well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2011-12	Cum	3939.41		

4	42.12	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459cum, with superplastisiser @ 3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof	**Cum**	**5296.75**		
5	42.12	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5 m including cost of all labour complete as per specifications. (P-6,I-2.10 PWD SR 2011-12)	Cum	97.20		
6	16.85	Providing T.M.T steel reinforcement for R.C.C work including straightening cutting, bending, hooking, placing wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of ,materials, labor HOM of machinery completed as per specifications. (P.No.19/4.46PWD SR 2011-12)	Qtl	7347.82		
7	117.00	Providing and laying 10cms thick precast R.C.C. slabs (DATA RATE)	**Sqm**	**1500.00**		
8	444.60	Providing and removing centering, shuttering, shuttering, strutting, propping etc.., and removal of form work for vertical surface such as walls at any thickness, including attached plasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. (P.No.17/4.31 PWD SR 2011-12)	**Sqm**	221.40		

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ .....( )
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-92

Signature of the Contractor
Reg. No.
Postal Address

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92